BRUHATH BANGALORE MAHANAGARA PALIKE
ITEMWAR TENDER SCHEDULE-B
DTS

Issued to Sri

TEND NO:
ITEM NO:
Orginal/Duplicate

NAME OF WORK: Providing & fixing M.S. street Name Boards @ Muthyalanagara & Mohankumar ugara areas in Ward No.17

Sl. No	Quantity	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	39.37	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications	cum		
2	9.84	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40 mm and down size graded granite metal machine mixed, concred laid in layers not exceeding 15 cms. thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machineries, curing complete as per specifications.	cum		
3	45.93	Providing and laying in position plain cement concrete of nominal mix 1:1.5:3 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum		
4	324.00	Supplying of MS steel name boards as per approved design and specification complete with all lead & lift as per the direction of the engineer in charge (data rate)	sqm		
5	439.02	Painting:-Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.	cum		
6	16200.00	Painting New Letter and Figures of any Shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specifications. (*i) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half)	sqm		

-	6200.00	Painting new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specifications. (*iii) English and Roman - Hyphen and the like not to be measured and paid for of size 450 x 200 x 400 mm	nos		
8	39.37	Conveying the excavated earth to a distance of 10 kms by using the vehicle including loading and unloading charges etc. complete.	cum		

No of Corrections NIL

Signature of the contractor

DTS Approved

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
RRNagara Division
B.B.M.P

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP